




Owner of Record

James M. Ridge Trustee
DR 379, Pg 175

Basis of Bearings


R/W of ST. RD. 37, Rotated to
Highway Plan Bearings
Project ST-F-428(20)


Note:

□ = 5/8" Rebar w/ Cap Set

■ = Stone Found

I, Steven W. Archer, hereby certify
that this plat represents a survey
conducted under my direct super-
vision on March 31, 1994.


Steven W. Archer
Registered Land Surveyor #8700094
State of Indiana




Steve Archer
205 N. College Ave.
Suite 512
Bloomington, IN 47404
(812) 334-8941

DESCRIPTION: A part of the Northwest quarter of the Northwest quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows to-wit:

From the Northwest corner of Section 33, Township and Range aforesaid; traverse thence South 358.5 feet to the POINT OF BEGINNING for this description; thence traverse South 961.5 feet; thence traverse East, 330 feet; thence traverse North 1320 feet; thence traverse West, 87 feet; thence traverse 358.5 feet; thence traverse West, 243 feet back to the point of beginning. Containing in all 8.0 acres more or less.

SUBJECT TO: All legal highways, easements and rights-of-way of record.


PREPARED BY: John E. Drapalik, L.S.



6810 N. SHOWERS ROAD

SCT 9 SW 1/4

"HOUSE DETAIL"
SCALE 1" = 30'



Raymond Graham
Raymond Graham

R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike

Bloomington, Indiana November 9, 1989

DESCRIPTION:

A part of the Southeast quarter of the Southwest quarter of Section 33, Township 10 North, Range 1 West, and a part of the Northwest quarter of the Northeast quarter of Section 4, Township 9 North, Range 1 West, Monroe County, Indiana, as recorded in Deed Record 322 at page 376 and being more particularly described as follows:

A part of the Southeast quarter of the Southwest quarter in Section 33, Township 10 North, Range 1 West, and a part of the Northwest quarter of the Northeast quarter in Section 4, Township 9 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point that is 708.15 feet South of the Northwest corner of the Northwest quarter of Showers Road, thence running with said centerline North 00 degrees 21 minutes 28 seconds West for 457.44 feet, thence North 05 degrees 09 minutes 25 seconds East for 63.86 feet, thence North 10 degrees 57 minutes 51 seconds East for 61.41 feet, thence North 26 degrees 16 minutes 26 seconds East for 58.59 feet and to the intersection of Showers road and Wylie road, thence running with said Wylie road centerline South 78 degrees 16 minutes 01 second East for 77.54 feet, thence leaving said road centerline and running South 00 degrees 21 minutes 28 seconds East for 740.33 feet, thence West for 200.00 feet and to the point of beginning. Containing in all 3.18 acres, more or less. Subject to a 25.00 foot easement from the centerline of said Showers Road and Wylie road for County Highway right-of-way.

CERTIFICATION:

I hereby certify that this plat as shown is a true and complete survey of the described property, and further certify that all improvements are wholly within the boundaries of said described property, and that the said improvements do not encroach upon any other property, nor are there any encroachments from any other property on said surveyed property.

NW CORNER
NW 1/4, NE 1/4
SECTION 4
T9N, R1W


N10°57'51"E

N05°09'25"E

SHOWERS ROAD

SHOWERS ROAD

708.15 SOUTH
NW CORNER
NW 1/4, NE 1/4
SECTION 4
T9N, R1W



SCALE
1" = 100'

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor


SURVEYOR LOCATION REPORT

THIS REPORT IS BASED ON LIMITED ACCURACY DATA AND THEREFORE NO DATA HEREIN SHOULD BE USED FOR CONSTRUCTION OR ESTABLISHING BOUNDARY OR FENCE LINES.

PROPERTY ADDRESS: Lawson Rd.
PROPERTY DESCRIPTION: see below

Sec 33 Washington

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305



A part of the Northwest Quarter of the Northwest Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning at the Northwest Corner of said Quarter Quarter Section, thence East 243 feet, thence South 358.5 feet, thence West 243 feet, thence North 358.5 feet to the point of beginning.

Containing 2 acres, more or less.

DESIGNATED PARTIES

MORTGAGEE
OR ASSIGNEES:
TITLE CO.:
OTHER:

FILED

JUN 01 1987

Rodney J. Brown
Monroe County, Indiana


I, the undersigned, an Indiana Registered Land Surveyor, hereby certify that on the date shown, I supervised the inspection of the real estate described herein at the Address indicated. **THIS LOCATION REPORT WAS PREPARED FOR USE BY THE DESIGNATED PARTIES ONLY AND FOR NO ONE ELSE. THE ACCURACY OF THE LOCATION DATA SHOWN IS LIMITED TO THAT REQUIRED BY THE INDIANA "SURVEYOR LOCATION REPORT" MINIMUM REQUIREMENTS UNLESS OTHERWISE SPECIFIED AND EXPLAINED ON THIS DOCUMENT. IF A MORE ACCURATE OR DETAILED LAND SURVEY IS DESIRED OR IF CORNER MONUMENTS ARE REQUIRED, AN INDIANA LAND TITLE SURVEY SHOULD BE ORDERED.**

I further certify that to the best of my knowledge this Location Report conforms with the **SURVEYOR LOCATION REPORT** Minimum Requirements, as adopted by the Indiana Society of Professional Land Surveyors, Inc., on January 29, 1981, and approved by the Title Underwriters of Indiana, Inc., on March 20, 1981.

CERTIFICATION DATE 4-4-86

SURVEYORS SIGNATURE


SURVEYORS JOB NO. MD02040186



Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

P.O. Box 90
Ellettsville, Indiana 47-29
Phone: 812-876-2305
Sec 33



SCALE: 1" = 200'

I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a land survey completed under my supervision on October 1, 1979; that all the monuments shown thereon actually exist; and that their location and type are to the best of my knowledge accurately shown.

Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. S0114

A part of the Northeast Quarter of the Northeast Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning at a point 42.67 feet South and 561.26 feet West from the Northeast Corner of said Section, thence along the center line of a County Road (presently referred to as Sample Road) the following courses and distances: South Sixty-eight (68) Degrees, Sixteen (16) Minutes, Forty (40) Seconds East 12.43 feet, thence South Fifty-nine (59) Degrees, Thirteen (13) Minutes, Forty-six (46) Seconds East 287.57 feet, thence leaving said center line South Zero (00) Degrees, Eight (08) Minutes, Thirty-four (34) Seconds East 768.09 feet, thence running West 258.26 feet, thence North Zero (00) Degrees, Eight (08) Minutes, Thirty-four (34) Seconds West 919.81 feet to the place of beginning.

Containing 5.01 acres, more or less.

Working for H. Westcott Quarter Sec. 33
Ellettsville to Ellettsville
8-12-79

103 West Temperance
P.O. Box 96 *Sec 33*
Ellettsville, Indiana 47429
Phone: 812-876-2305

Survey map showing a tract of 7.78 ± ACRES.

Boundaries and bearings/distances:


- North boundary: $N 89^{\circ} 33' 16'' E$, 432.01' (County Road)
- East boundary: $S 62^{\circ} 52' 40'' E$, 29.00' and $S 62^{\circ} 16' 41'' E$, 66.97' (County Road)
- South boundary: $S 00^{\circ} 00' 34'' E$, 520.73'
- West boundary: $WEST$, 572.11'
- Left boundary: $N 06^{\circ} 24' 42'' W$, 460.24' (East R/W St. Rd.)
- Top-left boundary: $N 00^{\circ} 26' 45'' W$, 35.00'
- Inner left boundary: $N 37^{\circ} 03' 08'' E$, 78.05'

Scale: 1" = 200'

P.O.B.: 42.67' South & 561.23' West from NE Corner of Sec. 33, T-10-N, R-1-W

e are to the best of my knowle


Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. 50114



Beginning at a point 42.67 feet South and 561.26 feet West from the Northeast Corner of said Section, thence running South Zero (00) Degrees, Eight (08) Minutes, Thirty-four (34) Seconds East 526.73 feet, thence running West 572.11 feet to the East Right of Way of State Road Number Thirty-seven (37), thence along said State Road Right of Way the following courses and distances: North Eight (08) Degrees, Twenty-four (24) Minutes, Forty-two (42) Seconds West 468.24 feet, thence North Thirty-seven (37) Degrees, Eight (08) Minutes, Eight (08) Seconds East 78.05 feet, thence North Zero (00) Degrees, Twenty-six (26) Minutes, Forty-five (45) Seconds West 35.00 feet to the North Line of said Section and to the County Road (presently referred to as Sample Road), thence leaving said East Right of Way and along said North Section Line and along said County Road North Eighty-nine (89) Degrees, Thirty-three (33) Minutes, Sixteen (16) Seconds East 432.01 feet, thence leaving said North Line and along the center line of said County Road the following courses and distances: South Eighty-two (82) Degrees, Fifty-two (52) Minutes, Forty-eight (48) Seconds East 99.00 feet, thence South Sixty-eight (68) Degrees, Sixteen (16) Minutes, Forty-one (41) Seconds East 66.97 feet to the place of beginning.

Containing 7.78 acres, more or less.

Washington = tomorrow given me. 23
 Give to (delete) dear to the love
 8-12-79


Part of the Northwest quarter of the Northwest quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows: Beginning at a 5/8 inch rebar with cap found marking the Northeast corner of said quarter quarter section; thence South Zero (00) degrees, Thirteen (13) minutes, Six (06) seconds East One Thousand Three Hundred Nine and Seventy-three Hundredths (1,309.73) feet to a wood fence post found marking the Southeast corner of said quarter quarter section; thence along the South line of said quarter quarter North Eighty-nine (89) degrees, Twenty (20) minutes, Thirty-two (32) seconds West Three Hundred Thirty (330.00) feet to a wood fence post found; thence North Zero (00) degrees, Thirteen (13) minutes, Eight (08) seconds West One Thousand Three Hundred Nine and Sixteen Hundredths (1,309.16) feet to a P.K. nail set on the North line of said quarter quarter and in Lawson Road; thence along said road and North line South Eighty-nine (89) degrees, Twenty-six (26) minutes, Thirty-three (33) seconds East Three Hundred Thirty (330.00) feet to the point of beginning. Containing Nine and Ninety-two Hundredths (9.92) acres, more or less. (Per survey of Steven W. Archer, RLS 8700094, dated September 15, 1998.)

Survey of Steven W. Archer, RLS 8700094, dated September 15, 1998.

back 33

Sec 33 Wash

W Richard ^{Gledys} Moore




Scale 1"=100'

Pt of beginning
593.35' North & 1201.65' East
of SW corner of SE 1/4-SW 1/4
Sect 33, T10N, R1W

DESCRIPTION:

A part of the Southeast quarter of the Southwest quarter and a part of the Southwest quarter of the Southeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point that is 593.35 feet North and 1201.65 feet East of the Southwest corner of the said Southeast quarter of the Southwest quarter of said Section 33, said point also being on the East right-of-way of State Road Number 37, thence running with the said right-of-way North 25 degrees 46 minutes East for 240.00 feet, thence leaving the said right-of-way and running South 88 degrees 05 minutes East for 531.40 feet, thence South 13 degrees 53 minutes West for 224.70 feet, thence North 88 degrees 05 minutes West for 581.90 feet and to the point of beginning. Containing in all 2.80 acres, more or less.



Raymond Graham
RAYMOND GRAHAM
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
March 14, 1986

Raymond Graham
Raymond Graham
Updated September 19, 1991

Davis, Jeffrey

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

LEGAL DESCRIPTION

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305
FAX: 812-876-2309

A part of the Southwest Quarter of the Southeast Quarter and a part of the Southeast Quarter of the Southwest Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, and also a part of the Northwest Quarter of the Northeast Quarter of Section Four (4), Township Nine (9) North, Range One (1) West, Monroe County, Indiana more particularly described as follows:

Beginning in the Center Line of a County Road 2.51 feet South and 2333.56 feet West from the Southeast Corner of said Section Thirty-three (33), thence on said Center Line South Eighty-one (81) Degrees, Twenty-eight (28) Minutes, Fifty-one (51) Seconds West 54.87 feet, thence leaving said Center Line North Fifteen (15) Degrees, Forty-eight (48) Minutes, Thirty (30) Seconds East 208.01 feet, thence North Sixty-two (62) Degrees, Twenty-six (26) Minutes, Seven (07) Seconds West 225.22 feet, thence North Seventeen (17) Degrees, Fifteen (15) Minutes, Twenty-one (21) Seconds East 30.00 feet, thence North Seventy-four (74) Degrees, Forty-four (44) Minutes, Thirty-nine (39) Seconds West 120.00 feet, thence North Seventeen (17) Degrees, Fifteen (15) Minutes, Twenty-one (21) Seconds East 60.00 feet to a rebar, thence North Twenty-one (21) Degrees, Four (04) Minutes East 192.12 feet to a rebar, thence South Eighty-six (86) Degrees, Twenty-nine (29) Minutes East 379.27 feet to a rebar and an existing fence line, thence along said fence line South Fifteen (15) Degrees, Forty-eight (48) Minutes, Thirty (30) Seconds West 596.35 feet to the point of beginning.

Containing 3.00 acres more or less.

2.99 acres in Section 33, more or less.


0.01 acres in Section 4, more or less.

*Sec 33 West -
✓
Sec 4 Bluff -
✓*

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and the enclosed descriptions correctly represent a land survey completed under my supervision on July 28, 1983; that all the monuments shown thereon actually exist, and that their location and type are to the best of my knowledge accurately shown.

NOTE

EXISTING 6.29± ACRES TO BE PARCELIZED INTO 2 LOTS. EXISTING SEPTIC PERMIT #6852 IS FOR PROPOSED LOT 'B'. THIS APPLICATION IS FOR NEW LOT 'A'

S0114
Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. S0114

FARM FIELD IS IMMEDIATELY EAST OF PROPERTY

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor


103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305

SURVEYOR LOCATION REPORT

THIS REPORT IS BASED ON LIMITED ACCURACY DATA AND THEREFORE NO DATA HEREIN SHOULD BE USED FOR CONSTRUCTION OR ESTABLISHING BOUNDARY OR FENCE LINES.

PROPERTY ADDRESS: 117 East Wylie Road

PROPERTY DESCRIPTION: See attached legal description



DESIGNATED PARTIES

**MORTGAGEE
OR ASSIGNEES:
TITLE CO.:
OTHER:**

This property is not located in a flood hazard area.

I, the undersigned, an Indiana Registered Land Surveyor, hereby certify that on the date shown, I supervised the inspection of the real estate described herein at the Address indicated. **THIS LOCATION REPORT WAS PREPARED FOR USE BY THE DESIGNATED PARTIES ONLY AND FOR NO ONE ELSE. THE ACCURACY OF THE LOCATION DATA SHOWN IS LIMITED TO THAT REQUIRED BY THE INDIANA "SURVEYOR LOCATION REPORT" MINIMUM REQUIREMENTS UNLESS OTHERWISE SPECIFIED AND EXPLAINED ON THIS DOCUMENT. IF A MORE ACCURATE OR DETAILED LAND SURVEY IS DESIRED OR IF CORNER MONUMENTS ARE REQUIRED, AN INDIANA LAND TITLE SURVEY SHOULD BE ORDERED.**


I further certify that to the best of my knowledge this Location Report conforms with the **SURVEYOR LOCATION REPORT** Minimum Requirements, as adopted by the Indiana Society of Professional Land Surveyors, Inc., on January 29, 1981, and approved by the Title Underwriters of Indiana, Inc., on March 20, 1981.

CERTIFICATION DATE

January 30, 1990

SURVEYORS SIGNATURE

SURVEYORS FOR NO



TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96 *Sec 33*
Ellettsville, Indiana 47429
Phone: 812-876-2305

DESCRIPTION

A part of the Southwest Quarter of the Southeast Quarter and a part of the Southeast Quarter of the Southwest Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, and also a part of the Northwest Quarter of the Northeast Quarter and a part of the Northeast Quarter of the Northeast Quarter of Section Four (4), Township Nine (9) North, Range One (1) West, Monroe County, Indiana more particularly described as follows:

Beginning in the Center Line of a County Road 2.51 feet South and 2333.56 feet West from the Southeast Corner of said Section Thirty-three (33), thence on said Center Line South Eighty-one (81) Degrees, Twenty-eight (28) Minutes, Fifty-one (51) Seconds West 54.87 feet to the True Place of Beginning, thence leaving said Center Line North Fifteen (15) Degrees, Forty-eight (48) Minutes, Thirty (30) Seconds East 208.01 feet, thence North Sixty-two (62) Degrees, Twenty-six (26) Minutes, Seven (07) Seconds West 225.22 feet, thence North Seventeen (17) Degrees, Fifteen (15) Minutes, Twenty-one (21) Seconds East 30.00 feet, thence North Seventy-four (74) Degrees, Forty-four (44) Minutes, Thirty-nine (39) Seconds West 120.00 feet, thence South Seventeen (17) Degrees, Fifteen (15) Minutes, Twenty-one (21) Seconds West 56.47 feet, thence South Seventeen (17) Degrees, twenty-seven (27) Minutes, Zero (00) Seconds West 151.60 feet, thence South Seventeen (17) Degrees, Zero (00) Minutes, Twenty-seven (27) Seconds West 125.44 feet, thence South Seventeen (17) Degrees, Zero (00) Minutes, Zero (00) Seconds West 222.87 feet to the Center Line of the aforementioned County Road, thence along said Center Line the following courses and distances:

South Fifty-three (53) Degrees, Twenty-six (26) Minutes, Nineteen (19) Seconds East 26.19 feet, thence North Seventy-six (76) Degrees, Forty-seven (47) Minutes, Forty-four (44) Seconds East 85.66 feet, thence North Fifty-six (56) Degrees, Fifty-seven (57) Minutes, Twenty-five (25) Seconds East 268.99 feet, thence North Eighty-one (81) Degrees, Twenty-eight (28) Minutes, Fifty-one (51) Seconds East 83.74 feet to the Place of Beginning.

Containing 3.14 Acres, more or less.

Containing 0.82 Acres, more or less in Section Four (4).

Containing 2.32 Acres, more or less in Section Thirty-three (33).

FILED
JUN 18 1984


Vk Simpson
Auditor Monroe County, Indiana

Washington
Doc
ab

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47425
Phone: 812-876-2305



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and the enclosed descriptions correctly represent a land survey completed under my supervision on July 28, 1983; that all the monuments shown thereon actually exist, and that their location and type are to the best of my knowledge accurately shown.


NOTE

EXISTING 6.29 ± ACRES TO BE PARCELIZED INTO 2 LOTS. EXISTING SEPTIC PERMIT #6852 IS FOR PROPOSED LOT 'B'. THIS APPLICATION IS FOR NEW LOT 'A'

Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. 50114

FARM FIELD
IS IMMEDIATELY
EAST OF PROPERTY

PART SE 1/4 SW 1/4, SECTION 33, T10N, R1W



DESCRIPTION:

A part of the Southeast quarter of the Southwest quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at the Northwest corner of the Northwest quarter of the Northeast of Section 4, Township 9 North, Range 1 West, Monroe County, Indiana, thence running on the section and township line dividing Section 33, Township 10 North, Range 1 West and Section 4, Township 9 North, Range 1 West, North 89 degrees 58 minutes 24 seconds East for 85.02 feet and to the point of beginning, said point being in the centerline of Showers road, thence leaving said road and continuing on said section and township line North 89 degrees 58 minutes 24 seconds East for 118.40 feet, thence leaving said line and running North 00 degrees 21 minutes 28 seconds West for 32.08 feet and to the centerline of Wylie road, thence running with said Wylie road North 78 degrees 16 minutes 01 second West for 77.54 feet and to the intersection of Wylie road and Showers road, thence running with the centerline of Showers road South 42 degrees 49 minutes 18 seconds West for 58.59 feet, thence South 26 degrees 16 minutes 26 seconds West on said centerline for 5.50 feet and to the point of beginning. Containing in all 0.09 acre, more or less. Subject to a 25.00 foot easement from the centerline of said Wylie road and Showers road for County Highway right-of-way.




Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
November 10, 1989

SE $\frac{1}{4}$ SW $\frac{1}{4}$

NW CORNER
NW 1/4, NE 1/4
SECTION 4
T9N, R1W



Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana November 9, 1989


DESCRIPTION:

A part of the Southeast quarter of the Southwest quarter of Section 33, Township 10 North, Range 1 West, and a part of the Northwest quarter of the Northeast quarter of Section 4, Township 9 North, Range 1 West, Monroe County, Indiana, as recorded in Deed Record 322 at page 376 and being more particularly described as follows:

A part of the Southeast quarter of the Southwest quarter in Section 33, Township 10 North, Range 1 West, and a part of the Northwest quarter of the Northeast quarter in Section 4, Township 9 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point that is 708.15 feet South of the Northwest corner of the Northwest quarter of the Northeast quarter in Section 4, Township 9 North, Range 1 West and in the centerline of Showers Road, thence running with said centerline North 00 degrees 21 minutes 28 seconds West for 457.44 feet, thence North 05 degrees 09 minutes 25 seconds East for 63.86 feet, thence North 10 degrees 57 minutes 51 seconds East for 61.41 feet, thence North 26 degrees 16 minutes 26 seconds East for 146.97 feet, thence North 42 degrees 49 minutes 18 seconds East for 58.59 feet and to the intersection of Showers road and Wylie road, thence running with said Wylie road centerline South 78 degrees 16 minutes 01 second East for 77.54 feet, thence leaving said road centerline and running South 00 degrees 21 minutes 28 seconds East for 740.33 feet, thence West for 200.00 feet and to the point of beginning. Containing in all 3.18 acres, more or less. Subject to a 25.00 foot easement from the centerline of said Showers Road and Wylie road for County Highway right-of-way.

CERTIFICATION:

I hereby certify that this plat as shown is a true and complete survey of the described property, and further certify that all improvements are wholly within the boundaries of said described property, and that the said improvements do not encroach upon any other property, nor are there any encroachments from any other property on said surveyed property.



777.30 W 131
NE CORNER
NW 1/4, NW 1/4
SECTION 33
T10N, R1W

*excellent
adjoining property*


*Set 3 m
W
Lawson Rd*

DESCRIPTION:

A part of the Northwest quarter of the Northwest quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows:
Beginning at a point that is 744.30 feet West of the Northeast corner of said quarter quarter and in Lawson Road; thence running South 16 degrees 03 minutes 55 seconds West for a distance of 721.20 feet; thence running South 08 degrees 28 minutes 08 seconds West for a distance of 74.62 feet; thence South 01 degree 16 minutes 39 seconds West for a distance of 350.74 feet; thence South 11 degrees 22 minutes 33 seconds East for 192.81 feet; thence West for 30.60 feet; thence North 11 degrees 22 minutes 33 seconds West for 189.89 feet; thence North 01 degree 16 minutes 39 seconds East for 355.95 feet; thence North 08 degrees 28 minutes 08 seconds East for 78.52 feet; thence North 16 degrees 03 minutes 55 seconds East for 714.54 feet to a point in Lawson Road; thence East in Lawson Road for 31.24 feet to the point of beginning.
Containing 0.94 acres, more or less.

Raymond Graham


RAYMOND GRAHAM
RPE 8409 LS 9978 Indiana
3215 N Smith Pike
Bloomington, Indiana
December 29, 1988



FILED

AUG 18 1989

Margaret Cook
Auditor Monroe County, Indiana



EXECUTOR'S DEED

BYRON K. SMITH, as personal representative of the Estate of Cleo K. Smith, deceased, which estate is under the supervision of the Circuit Court of Monroe County, under Estate No. 53C01-8808-ES-00133, in the Office of the Clerk of the Circuit Court of Monroe County, Indiana, pursuant to an order of the Monroe Circuit Court of Monroe County, Indiana, dated on the 1st day of February, 1989, for good and sufficient consideration, CONVEYS TO:

SHARON J. CRANE and DIANNE E. MITCHELL,
jointly, not as tenants in common, but
as joint tenants with rights of survivorship,
1855 Simpson Chapel, Bloomington, IN 47401

of Monroe County, State of Indiana, the following described real estate in Monroe County, State of Indiana, to-wit:

The Southwest quarter of the Northwest quarter of Section 33, Township 10 North, Range 1 West, containing 40 acres, more or less.

Also, a part of the Northwest quarter of the Northwest quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point that is 744.30 feet West of the Northeast corner of said quarter quarter and in Lawson Road; thence running South 16 degrees 03 minutes 55 seconds West for a distance of 721.20 feet; thence running South 08 degrees 28 minutes 08 seconds West for a distance of 74.62 feet; thence South 01 degree 16 minutes 39 seconds West for a distance of 350.74 feet; thence South 11 degrees 22 minutes 33 seconds East for 192.81 feet; thence West for 30.60 feet; thence North 11 degrees 22 minutes 33 seconds West for 189.89 feet; thence North 01 degree 16 minutes 39 seconds East for 355.95 feet; thence North 08 degrees 28 minutes 08 seconds East for 78.52 feet; thence North 16 degrees 03 minutes 55 seconds East for 714.54 feet to a point in Lawson Road; thence East in Lawson Road for 31.24 feet to the point of beginning. Containing 0.94 acres, more or less.

The Estate of Cleo K. Smith also conveys all of the interest of decedent in a passway as described in a deed from George L. Smith and his wife, Margaret Smith, to Oscar L. Smith, executed on the 25th day of October, 1915, as recorded in Deed Record 72, page 327, in the office of the Recorder of Monroe County, Indiana.

Subject to a non-exclusive driveway easement 30 feet in width as now located and used over and along the second above described real estate.

Subject to a 25-foot easement from the centerline of Lawson Road for County Highway right-of-way over the North side of said second above described real estate.

Subject to an easement executed on the 11th day of April, 1967, by Lucy Davidson to Indiana Statewide Rural Electric Cooperative, Inc., (The Hoosier Energy Division) and recorded on the 16th day of May, 1967, in Deed Record 177, pages 278-279, in the office of the Recorder of Monroe County, Indiana.

Subject to an Electric Pole Line Easement executed on the 18th day of June, 1956, by Charley A. Terrell and Leola Agnes Terrell to Public Service Company of Indiana, Inc., and recorded in Deed Record 120, page 467, in the office of the Recorder of Monroe County, Indiana.

Subject to an Electric Pole Line Easement executed on the 23rd day of May, 1956, by Cleo K. Smith, Mabel E. Smith, and Iris A. Smith to Public Service Company of Indiana, Inc., and recorded in Deed Record 120, page 262, in the office of the Recorder of Monroe County, Indiana.


TRI CO SURVEYING & MAPPING

Edmund O. Farkas
Registered Land Surveyor

(812) 876-2305

P. O. Box 98
Ellettsville, Indiana 47429

Agnes Tract #3
Washington Twp
Sec 33



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a land survey completed under my supervision on June 30, 1978; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown.

EDMUND O. FARKAS
REGISTERED
S0114
Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. S0114

A part of the Southeast Quarter of the Southwest Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning 452.99 feet North and 2691.87 feet West of the Southeast Corner of said Section, thence South Seventeen (17) Degrees and Six (06) Minutes West 114.02 feet to a pipe, thence North Sixty-four (64) Degrees and Thirty-eight (38) Minutes West 191.30 feet to a pipe on the East Right of Way line of State Road Number Thirty-seven (37), thence along said Line North Twenty-seven (27) Degrees and Fifty-four (54) Minutes East 107.69 feet to a pipe, thence leaving said Line South Sixty-six (66) Degrees and Twenty-four (24) Minutes East 170.25 feet to the pipe marking the place of beginning.

Containing 0.46 acres, more or less.

Mail tax statements to:

7275 N. Waypoint Rd.
Bloomington, In 47408

QUITCLAIM DEED

THIS INDENTURE WITNESSETH, That James M. Ridge, individually and James M. Ridge, Trustee under Declaration of Trust dated August 11, 1990, and Ralph D. Ridge and Lorraine Ridge, husband and wife, of Monroe County, in the State of Indiana, RELEASE AND QUITCLAIM to Steven Ridge and Michele Ridge, husband and wife, of Monroe County, in the State of Indiana, for and in consideration of One Dollar (\$1.00) and other good and valuable consideration not expressed herein, the receipt whereof is hereby acknowledged, the following described Real Estate in Monroe County, in the State of Indiana, to-wit:

Part of the Southwest quarter of the Northeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, and more particularly described as follows: Beginning at a 5/8 inch rebar with cap set South 89 degrees 08 minutes 31 seconds East 575.22 feet from a stone found marking the Northwest corner of said quarter quarter section; thence South 89 degrees 08 minutes 31 seconds East 550.00 feet to a 5/8 inch rebar with cap set on the Westerly right-of-way line of State Road No. 37; thence along said right-of-way line the following two bearings and distances: South 08 degrees 46 minutes 50 seconds West 54.89 feet to a 5/8 inch rebar with cap set; thence South 15 degrees 09 minutes 52 seconds West 489.78 feet to a 5/8 inch rebar with cap set; thence North 00 degrees 57 minutes 14 seconds West 94.86 feet to a stone found; thence North 89 degrees 28 minutes 45 seconds West 412.62 feet to a 5/8 inch rebar with cap set; thence North 00 degrees 05 minutes 54 seconds East 436.61 feet to the point of beginning. Containing 5.00 acres more or less.

SUBJECT TO a 50 foot wide roadway and utility easement being described as follows: Beginning at the Northwest corner of the above described tract; thence South 89 degrees 08 minutes 31 seconds East 550.00 feet to the Westerly right-of-way of State Road No. 37; thence along said right-of-way South 08 degrees 46 minutes 50 seconds West 50.48 feet; thence North 89 degrees 08 minutes 31 seconds West 542.38 feet to the West line of the above described tract thence North 00 degrees 05 minutes 54 seconds East 50.00 feet to the point of beginning.

In Witness Whereof, the said grantors has hereunto set their hands and seals this 2nd day of June, 1994.

James M. Ridge
James M. Ridge

Ralph D. Ridge
Ralph D. Ridge

Lorraine Ridge
Lorraine Ridge

5.00
3.88
1.12

309
79
388
112
500

Mc 33 Washington

Ridge

1/2

STATE OF INDIANA, COUNTY OF MONROE, SS:

Before me, the undersigned, a Notary Public in and for said County and State, this 2nd day of June, 1994, came James M. Ridge, individually, and James M. Ridge as Trustee under Declaration of Trust dated August 11, 1990, and Ralph D. Ridge and Lorraine Ridge, husband and wife, and acknowledged the execution of the foregoing instrument.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my official seal.

Marilyn Galvan
Notary Public

Residing in Greene County

My commission expires:

11-3-94

TRI CO SURVEYING & MAPPING


Edmund O. Farkas
Registered Land Surveyor

(812) 876-2305

P. O. Box 96
Ellettsville, Indiana 47429

Sec 33

SCALE: 1" = 40'




I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a survey completed under my supervision on June 30, 1978; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown. I also certify that all improvements upon said surveyed property do not encroach upon adjacent properties, nor are there any encroachments upon said surveyed property by adjacent properties.

FILED

JUL 27 1978

John W. Davis
Auditor Monroe County, Indiana



A part of the Southeast Quarter of the Southwest Quarter and a part of the Southwest Quarter of the Southeast Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning 452.99 feet North and 2691.87 feet West of the Southeast Corner of said Section, thence North Sixty-six (66) Degrees and Twenty-four (24) Minutes West 170.25 feet to a pipe on the East Right of Way Line of State Road Number Thirty-seven (37), thence along said Line North Twenty-eight (28) Degrees and Twenty (20) Minutes East 107.16 feet to a pipe, thence leaving said Line South Eighty-six (86) Degrees and Twenty-nine (29) Minutes East 167.95 feet to a pipe, thence South Twenty-two (22) Degrees and Twenty (20) Minutes West 164.50 feet to the place of beginning.

Containing 0.51 acres, more or less.

Purcell, Wm W. & Inez E.

to

McConnell, Wiland V & Jonetta

1.06 out of 5.60 A.


.45 out of 1.42 A.

.51

33-10-1W


33-10-1W

WASHINGTON



DESCRIPTION:


A part of the Northeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point on the East line of the said Section 33, said point being 382.00 feet South of the Northeast corner of the said quarter section and in the centerline of Sample road; thence leaving the said road centerline and running along the said East line South for 1349.60 feet; thence running West for 303.11 feet; thence running North for 1032.34 feet; thence running East for 200.00 feet; thence running North for 376.79 feet and to the centerline of said Sample Road; thence with the said road centerline running South 60 degrees East for 119.06 feet and to the point of beginning. Containing in all 7.74 acres, more or less. Subject to a 25.00 foot easement from the centerline of said Sample Road for County Highway right-of-way.



Raymond Graham
 RAYMOND GRAHAM
 R.P.E. 8409 L.S. 9978 IND
 3215 N. Smith Pike
 Bloomington, Indiana
 September 18, 1989

FILED
 OCT 03 1989


Margaret Cook
 Auditor Monroe County, Indiana



DESCRIPTION:

A part of the Northeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point in the centerline of Sample Road; said point being 322.47 feet South and 103.11 feet West of the Northeast corner of the said quarter section; thence leaving the said road centerline and running South for 376.79 feet; thence running West for 200.00 feet; thence running North for 492.26 feet and to the centerline of the said Sample Road; thence running over and along the said road centerline South 60 degrees East for 230.94 feet and to the point of beginning. Containing in all 2.26 acres, more or less.

Subject to a 25.00 foot easement from the centerline of Sample Road for County Highway right-of-way.



Raymond Graham
RAYMOND GRAHAM
R.P.E. 8409 L.S. 9978 IND
3215 N. Smith Pike
Bloomington, Indiana
September 18, 1989

FILED
OCT 03 1989

Margaret Cook
Auditor Monroe County, Indiana

COPY

WARRANTY DEED

Auditor

Recorder

Duplicate #

Post Office Address of Grantee:
281 E. Sample Road
Bloomington, IN 47408

THIS INDENTURE WITNESSETH, That, RONALD L. GILLILAND and JANICE K. GILLILAND, husband and wife, ("Grantor"), of Monroe County, in the State of Indiana, CONVEY AND WARRANT to RONALD L. GILLILAND and JANICE K. GILLILAND, husband and wife, of Monroe County, in the State of Indiana, for the sum of One Dollar (\$1.00) and other valuable consideration, the receipt of which is hereby acknowledged, the following described real estate in Monroe County, in the State of Indiana:

A part of the Northeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point in the centerline of Sample Road; said point being 322.47 feet South and 103.11 feet West of the Northeast corner of said quarter section; thence leaving the said road centerline and running South for 376.79 feet; thence running West for 200.00 feet; thence running North for 492.26 feet and to the centerline and of the said Sample road; thence running over and along the said road centerline South 60 degrees East for 230.94 feet and to the point of beginning. Containing in all 2.26 acres, more or less.

Subject to a 25.00 foot easement from the centerline of Sample Road for County Highway right-of-way.


Subject to all taxes.

IN WITNESS WHEREOF, Grantor has executed this Deed this

3rd day of October, 19 89.

Ronald L. Gilliland
RONALD L. GILLILAND

Janice K. Gilliland
JANICE K. GILLILAND



DESCRIPTION:

A part of the Southeast quarter of Section 33, Township 10 North, Range 1 West Monroe County, Indiana, bounded and described as follows: Beginning at the Southeast corner of said Section 33 and in Wylie Road; thence running West along the South line of Section 33 and in Wylie Road for a distance of 1053.29 feet; thence leaving said South line and said Wylie Road and running North 11 degrees 15 minutes 33 seconds East for a distance of 1346.79 feet; thence running South 89 degrees 29 minutes 40 seconds East for a distance of 786.05 feet to the East line of Section 33, thence running South 00 degrees 11 minutes 17 seconds East along said East line for a distance of 1313.93 feet and to the point of beginning. Containing 27.82 acres, more or less. Subject to a 25.00 easement from the centerline of Wylie Road for County highway right-of-way.

Raymond Graham

RAYMOND GRAHAM
RPE 8409 LS 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
February 3, 1989



The grantor represents that in the deed to decedent herein for the first above described real estate, as recorded in Deed Record 115, page 91, in the office of the Recorder of Monroe County, Indiana, the grantors therein, Oscar L. Smith and Mabel E. Smith, reserved a life estate in said real estate, together with the rents and profits therefrom during their respective lifetimes; that the said Oscar L. Smith died intestate a resident of Monroe County, Indiana, on the 11th day of May, 1954, and that the said Mabel E. Smith died intestate a resident of Monroe County, Indiana, on the 26th day of September, 1958; that grantor is informed and verily believes that all the provisions of said life estates were fulfilled during the lifetimes of the grantors, Oscar L. Smith and Mabel E. Smith.

Subject to the second installment of taxes for 1988, due and payable in November, 1989, and all subsequent taxes.

IN WITNESS WHEREOF, the said BYRON K. SMITH, as personal representative of the Estate of Cleo K. Smith, deceased, has hereunto set his hand and seal this 1st day of February, 1989.

BYRON K. SMITH (SEAL)
BYRON K. SMITH, EXECUTOR OF THE
ESTATE OF CLEO K. SMITH, DECEASED

EXAMINED AND APPROVED IN OPEN
COURT, THIS 1st DAY OF
February, 1989.

James M. Dixon
JUDGE, MONROE CIRCUIT COURT

STATE OF INDIANA)

SS:

COUNTY OF MONROE)


Before me, the undersigned, a Notary Public in and for said County and State, personally appeared BYRON K. SMITH, as personal representative of the Estate of Cleo K. Smith, deceased, and acknowledged the execution of said deed to be his own free and voluntary act and deed for the uses and purposes expressed therein.

WITNESS my hand and seal this 1st day of February, 1989.

Sylvan W. Tackitt
SYLVAN W. TACKITT, NOTARY PUBLIC

My commission expires:
December 10, 1989.
Residing in Monroe County, IN.

SCALE FOR SECTION, } Each side large blue squares = 20 chains, 80 rods, 1320 feet; area of square 40 acres.
 660 Ft. = 1 Inch. } Each side small red squares = 5 chains, 20 rods, 330 feet; area of square 2½ acres.



SCALE FOR QUARTER SECTION, } Each side large blue squares = 10 chains, 40 rods, 660 feet; area of square 10 acres.
 330 Ft. = 1 Inch. } Each side small red squares = 2½ chains, 10 rods, 165 feet; area of square .625 of 1 acre.


PRONTO LAND MEASURE 660-330 MAP SHEET

PRONTO LAND MEASURE
 Copyright, 1950, James Hamilton Adair, Flint, Michigan

PLAT OF THE NORTHWEST QUARTER OF SECTION 33
 TOWNSHIP 10 NORTH RANGE 1 WEST, showing the
 10-acre tract herein abstracted in the Northwest
 Quarter of the Northwest Quarter of said Section 33
 IN RED.

LEE RIDGE TO GILBERT SNOOKS

NW CORNER NE 1/4, SW 1/4
SECTION 33, T10N, R1W



SCALE
1"=300'

DESCRIPTION:

A part of the Northeast quarter of the Southwest quarter and a part of the Northwest quarter, of the Southeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at the Northwest corner of the said Northeast quarter of the Southwest quarter of said Section 33; thence running East for 1320.00 feet; thence South for 198.00 feet; thence East for 455.28 feet; and to the centerline of a gravel roadway; thence with said centerline South for 79.88 feet; thence leaving said road centerline and running South 72 degrees 13 minutes 39 seconds West for 250.56 feet; thence South 80 degrees 29 minutes 27 seconds West for 311.19 feet; thence North 89 degrees 34 minutes 12 seconds West for 475.70 feet; thence South 06 degrees 12 minutes 26 seconds West for 251.75 feet; North 86 degrees 16 minutes 50 seconds West for 728.39 feet; thence North for 605.22 feet and to the point of beginning. Containing in all 17.57 acres, more or less.

Raymond Graham

RAYMOND GRAHAM
R.P.E. 8409 L.S. 9978 IND
3215 N. Smith Pike
Bloomington, Indiana
July 11, 1986



FILED
MAR 02 1990

Margaret Cook
Auditor Monroe County, Indiana

Purcell


Washington Twp Sec 33

TRI CO SURVEYING & MAPPING


Edmund O. Farkas
Registered Land Surveyor

(812) 876-2305

P. O. Box 96
Ellettsville, Indiana 47429



I, Edmund O. Farkas
hereby certify that I am a
Registered Land Surveyor, licensed
in compliance with the Laws of the State
of Indiana; that the above plat and following
description correctly represent a survey completed
under my supervision on June 30, 1978; that all the monuments shown thereon
actually exist and that their location and type are to the best of my knowledge
accurately shown.



A part of the Southeast Quarter of the Southwest Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:


Beginning 79.55 feet North and 2807.31 feet West from the Southeast Corner of said Section, thence North Sixty-four (64) Degrees and Zero (00) Minutes West 242.59 feet to the East Right of Way line of State Road Number Thirtv-seven (37), thence along said East Line North Twenty-seven (27) Degrees and Fifty-four (54) Minutes East 122.26 feet, to a pipe, thence leaving said East Line South Sixty-four (64) Degrees and Twenty-one (21) Minutes East 219.45 feet to a pipe, thence South Seventeen (17) Degrees and Thirteen (13) Minutes West 125.00 feet to the place of beginning. Containing 0.65 acres, more or less.

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305

Washington Sec. 33



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and the enclosed descriptions correctly represent a land survey completed under my supervision on July 28, 1983; that all the monuments shown thereon actually exist, and that their location and type are to the best of my knowledge accurately shown.

50114
Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. 50114

Wash Dec 33
Bryn Dec 4

Brenda Juddling PAGE 1

March 33
Brynlee 4

113 WYLIE ROAD

N74°44'39"W
N17°15'21"E
N62°26'07"W
N81°28'51"E
N56°57'25"E
N76°42'44"E
S53°26'19"E

120.00'
30.00'
225.22'
208.01'
88.74'
268.99'

OLD CEMETARY
STAKED ROCK WALLS
ONE STORY FRAME
WOOD
DRIVE
STONE
R/W
ROAD
WYLIE COUNTY

3.14 ACRES


SCALE 1"=50'

PLACE OF BEGINNING SECTION 33

2.51' SOUTH
2333.51' NW
SECTION 33
TION, R/W

See page Two for Description and Certification.

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
January 14, 1986



RAYMOND GRAHAM
R.P.E. 8409 L.S. 9978 IND
Recertified Nov. 28, 1988

 $\frac{1}{2}$


DESCRIPTION:

PAGE 2

A part of the Southwest quarter of the Southeast quarter and a part of the Southeast quarter of the Southwest quarter of Section 33, Township 10 North, Range 1 West, and also a part of the Northwest quarter of the Northeast quarter of Section 4, Township 9 North, Range 1 West, in Monroe County, Indiana, and more particularly described as follows: Beginning in the centerline of a County road 2.51 feet South and 2333.56 feet West from the Southeast corner of said Section 33; thence on said centerline South 81 degrees 28 minutes 51 seconds West 54.87 feet to the place of beginning; thence leaving said centerline North 15 degrees 48 minutes 30 seconds East 208.01 feet; thence North 62 degrees 26 minutes 07 seconds West 225.22 feet; thence North 17 degrees 15 minutes 21 seconds East 30 feet; thence North 74 degrees 44 minutes 39 seconds West 120 feet; thence South 17 degrees 15 minutes 21 seconds West 56.47 feet; thence South 17 degrees 27 minutes 00 seconds West 151.60 feet; thence South 17 degrees 00 minutes 27 seconds West 125.44 feet; thence South 17 degrees 00 minutes 00 seconds West 222.87 feet; to the centerline of the aforementioned County road; thence along said road the following courses and distances; South 53 degrees 26 minutes 19 seconds East 26.19 feet; thence North 76 degrees 47 minutes 44 seconds East 85.66 feet; thence North 56 degrees 57 minutes 25 seconds East 268.99 feet; thence North 81 degrees 28 minutes 51 seconds East 83.74 feet to the place of beginning. Subject to a 25 00 Foot easement from the centerline of said County Road for County Highway right-of-way. Containing in all 3.14 acres, more or less.

ENGINEER'S CERTIFICATION:

I hereby certify that this plat as shown is a true and complete survey of the described property, and further certify that all improvements are wholly within the boundaries of said described property, and that the said improvements do not encroach upon any other property, nor are there any encroachments from any other property on said surveyed property except for the Cemetery as shown on the above plat.



Raymond Graham
 Raymond Graham
 R.P.E. 8409 L.S. 9978 Indiana
 3215 N. Smith Pike
 Bloomington, Indiana
 January 14, 1986


Raymond Graham
 RAYMOND GRAHAM
 R.P.E. 8409 L.S. 9978 IND
 Recertified Nov. 28, 1988

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305

P.O.B. 79.55' NORTH,
2807.31' WEST FROM SE
CORNER SEC. 33, T-10-N
R-1-W



SEC. 33, T-10-N
SEC. 4, T-9-N

SCALE: 1" = 50'

FILED

DEC 3 1985

Robert J. Brown
Surveyor Monroe County, Indiana

A part of the Southeast Quarter of the Southwest Quarter of Section 33, Township 10 North, Range 1 West, and a part of the Northeast Quarter of the Northeast Quarter of Section 4, Township 9 North, Range 1 West, Monroe County, Indiana, and more particularly described as follows:

Beginning 79.55 feet North, and 2807.31 feet West from the Southeast Corner of said Section 33, thence South 64 Degrees Zero Minutes East 80.0 feet on the South Line of a 0.23 Acres tract of land, thence South 17 Degrees Zero Minutes West 222.87 feet, thence North 53 Degrees 26 Minutes West 84.68 feet, thence North 17 Degrees 13 Minutes East 207.03 feet to the place of beginning.

Containing 0.13 Acres more or less in Section 33, 0.26 Acres more or less in Section 4, 0.39 Acres more or less in all.


TRI CO SURVEYING & MAPPING

Edmund O. Farkas
Registered Land Surveyor


(812) 876-2305

P. O. Box 96
Ellettsville, Indiana 47429

Sec 33



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a land survey completed under my supervision on June 30, 1978; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown.



A part of the Southeast Quarter of the Southwest Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning 198.95 feet North and 2770.31 feet West from the Southeast Corner of said Section, thence North Sixty-four (64) Degrees and Twenty-one (21) Minutes West 219.45 feet to a pipe on the East Right of Way line of State Road Number Thirty-seven (37), thence along said Line North Twenty-seven (27) Degrees and Fifty-four (54) Minutes East 149.38 feet to a pipe, thence leaving said Line South Sixty-four (64) Degrees and Thirtv-eight (38) Minutes East 191.30 feet to a pipe, thence South Seventeen (17) Degrees and Thirteen (13) Minutes West 151.85 feet to the pipe marking the place of beginning.

Containing 0.71 acres, more or less.

TRI CO SURVEYING & MAPPING


Edmund O. Farkas
Registered Land Surveyor

(812) 878-2305


P. O. Box 96
Ellettsville, Indiana 47429

McConnell - Tract # 4
Washington Twp.
Sec 33

SCALE: 1" = 40'




I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a survey completed under my supervision on June 30, 1978; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown. I also certify that all improvements upon said surveyed property do not encroach upon adjacent properties, nor are there any encroachments upon said surveyed property by adjacent properties.



A part of the Southeast Quarter of the Southwest Quarter and a part of the Southwest Quarter of the Southeast Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning 452.99 feet North and 2691.87 feet West of the Southeast Corner of said Section, thence North Sixty-six (66) Degrees and Twenty-four (24) Minutes West 170.25 feet to a pipe on the East Right of Way Line of State Road Number Thirty-seven (37), thence along said Line North Twenty-eight (28) Degrees and Twenty (20) Minutes East 107.16 feet to a pipe, thence leaving said Line South Eighty-six (86) Degrees and Twenty-nine (29) Minutes East 167.95 feet to a pipe, thence South Twenty-two (22) Degrees and Twenty (20) Minutes West 164.50 feet to the place of beginning.

Containing 0.51 acres, more or less.




Owner of Record
James M. Ridge Trustee
DR 379, Pg 175

Basis of Bearings
R/W of ST. RD. 37, Rotated to
Highway Plan Bearings
Project ST-F-428(20)

Note:
□ = 5/8" Rebar w/ Cap Set
■ = Stone Found

I, Steven W. Archer, hereby certify
that this plat represents a survey
conducted under my direct super
vision on March , 1994.

Steven W. Archer
Registered Land Surveyor #87000
State of Indiana



091 30 1800
John W. Davis
Auditor Monroe County, Indiana

W
W

52c 73

LEE UTT
REGISTERED LAND SURVEYOR No. 50039, INDIANA
OFFICE PHONE 332-6366 HOME PHONE 825-5061
1604 SOUTH HENDERSON
BLOOMINGTON, INDIANA 47401


ELLER


May 31, 1977

Legal description: Tract # 1

A part of the Northwest quarter of the Northeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at the Southwest corner of said quarter quarter; thence from said point of beginning and with the South line of said quarter quarter and running South 89°-28'-48" East for 388.32 feet; thence leaving said South line and running North 00°-27'-14" West for 600.96 feet; thence South 83°-23'-20" West for 53.28 feet; thence South 75°-34'-36" West for 206.52 feet; thence North 89°-56'-24" West for 132.86 feet and to the West line of said Northwest quarter of the Northeast quarter; thence with the West line of said quarter quarter and running South 00°-14'-23" East for 539.99 feet and to the point of beginning. Containing 5.00 acres, more or less.

Also, the right to use a Twenty (20) foot non-exclusive easement, the centerline of said easement being described as follows: Beginning at a point on the East line of the above described tract, said point being 172.56 feet North of the Southeast corner of said above described tract; thence North 83°-46'-45" East for 307.93 feet; thence South 88°-01'-15" East for 148.86 feet; thence North 80°-12'-15" East for 252.74 feet and to the Westerly right-of-way line of State Road 37.


Lee Utt, R. L. S. # S0089, Indiana



LEE UTT
REGISTERED LAND SURVEYOR NO. 00089, INDIANA
OFFICE PHONE 552-6366 HOME PHONE 525-5561
1004 SOUTH HENDERSON
BLOOMINGTON, INDIANA 47401

PENDILL 2

May 31, 1977

Legal description: Tract # 2

Eller - Pendill


A part of the Northwest quarter of the Northeast quarter of Section 35, Township 10 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point on the South line of said quarter quarter said point of beginning being 388.32 feet East of the Southwest corner of said Northwest quarter of the Northeast quarter; thence from said point of beginning and with the South line of said quarter quarter and running South 89°-28'-48" East for 377.78 feet; thence leaving the South line of said quarter quarter and running North 01°-12'-30" West for 521.67 feet; thence North 74°-35'-38" West for 76.61 feet; thence North 62°-08'-32" West for 170.20 feet; thence South 83°-23'-20" West for 148.17 feet; thence South 00°-27'-14" East for 600.96 feet and to the point of beginning. Containing 5.00 acres, more or less.


Also, the right to use a Twenty (20) foot non-exclusive easement, said easement being described as follows:

Beginning at a point on the East line of the above described tract, said point being 180.25 feet North of the Southeast corner of said above described tract; thence South 88°-01'-15" East for 81.34 feet; thence North 80°-12'-15" East for 252.74 feet and to the Westerly right-of-way line of State Road 37.

Subject to a non-exclusive easement, Twenty (20) feet in width, the centerline of said easement being described as follows:

Beginning at a point on the West line of the above described tract, said point being 172.56 feet North of the Southwest corner of said above described tract; thence North 88°-46'-45" East for 307.93 feet; thence South 88°-01'-15" East for 67.52 feet and to a point on the East line of the above described tract, said point being 180.25 feet North of the Southeast corner of said tract.


Lee Utt, R. L. S. # S0089, Indiana



LEE UTT
REGISTERED LAND SURVEYOR No. 50089, INDIANA
OFFICE PHONE 332-6366 HOME PHONE 825-5961
1604 SOUTH HENDERSON
BLOOMINGTON, INDIANA 47401

ELLER
&
PENDILL


3


July 30, 1977

Legal description: Tract # 3 Eller - Pendill

A part of the Northwest quarter of the Northeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, bounded and described as follows:

Beginning at a point on the South line of said quarter quarter, said point of beginning being 766.10 feet East of the Southwest corner of said Northwest quarter of the Northeast quarter; thence from said point of beginning and with the South line of said quarter quarter and running South 89°-28'-48" East for 307.31 feet and to the Westerly right-of-way line of State Road 37; thence leaving the South line of said quarter quarter and with said right-of-way line and running North 01°-48'-35" West for 99.22 feet; thence North 10°-13'-34" East for 142.26 feet; thence North 18°-42'-02" East for 73.38 feet; thence North 59°-34'-28" East for 80.84 feet; thence North 05°-25'-50" East for 48.42 feet; thence North 50°-49'-47" West for 231.71 feet; thence leaving said right-of-way line and running South 88°-50' West for 32.05 feet; thence South 77°-03'-06" West for 154.33 feet; thence North 74°-35'-38" West for 78.53 feet; thence South 01°-12'-30" East for 521.67 feet and to the point of beginning. Containing 4.29 acres, more or less.


Lee Utt, R. L. S. # S0089, Indiana



Washington Twp - Sec. 33


SURVEYING & MAPPING

Edmund O. Farkas
Registered Land Surveyor

(812) 878-2305

P. O. Box 96
Ellettsville, Indiana 47429

Purcell John



I, Edmund O. Farkas
hereby certify that I am a
Registered Land Surveyor, licensed
in compliance with the Laws of the State
of Indiana; that the above plat and following
description correctly represent a survey completed
under my supervision on June 30, 1978; that all the monuments shown thereon
actually exist and that their location and bearings are to the best of my knowledge
accurately shown.

Edmund O. Farkas
Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. 10114

A part of the Southeast Quarter of the Southeast Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning 79.56 Feet North and 2807.31 Feet West from the Southeast Corner of said Section, thence North Sixty-four (64) degrees and Zero (00) Minutes West 242.59 Feet to the East Right-of-Way line of State Road Number Thirty-seven (37), thence along said East Line North Twenty-seven (27) Degrees and Fifty-four (54) Minutes East 122.26 Feet, to a line, thence leaving said East Line South Sixty-four (64) Degrees and Twenty-one (21) Minutes East 219.45 feet to a line, thence South Seventeen (17) Degrees and Thirteen (13) Minutes West 125.00 Feet to the place of beginning. Containing 0.65 acres, more or less.


Washington Imp. Sec. 33 *Aug 28* *Sec 33*

TRI CO SURVEYING & MAPPING

Edmund O. Farkas
Registered Land Surveyor

(812) 876-2305

P. O. Box 96
Ellettsville, Indiana 47429



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor, licensed in compliance with the Laws of the State of Indiana; that the above plat and following description correctly represent a land survey completed under my supervision on June 30, 1978; that all the monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown.



EDMUND O. FARKAS
S0114
Edmund O. Farkas
Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. S0114

A part of the Southeast Quarter of the Southwest Quarter of Section Thirty-three (33), Township Ten (10) North, Range One (1) West, Monroe County, Indiana, and more particularly described as follows:

Beginning 452.99 feet North and 2691.87 feet West of the Southeast Corner of said Section, thence South Seventeen (17) Degrees and Six (06) Minutes West 114.02 feet to a pipe, thence North Sixty-four (64) Degrees and Thirty-eight (38) Minutes West 191.30 feet to a pipe on the East Right of Way line of State Road Number Thirty-seven (37), thence along said Line North Twenty-seven (27) Degrees and Fifty-four (54) Minutes East 107.69 feet to a pipe, thence leaving said Line South Sixty-six (66) Degrees and Twenty-four (24) Minutes East 170.25 feet to the pipe marking the place of beginning.

Containing 0.46 acres, more or less.

WYLIE ROAD
JOB NO. 1217



S.E. CORNER OF SE 1/4,
SECTION 33, TION, RIW,
MONROE COUNTY, INDIANA.

Washington

W
H

WYLIE ROAD

OVERALL DESCRIPTION

JOB NUMBER 1217

Part of the Southeast Quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, more particularly described as follows:
Beginning at the southeast corner of said southeast quarter; thence NORTH 89 degrees 41 minutes 18 seconds WEST along the south line of said southeast quarter 2330.52 feet; thence NORTH 14 degrees 51 minutes 39 seconds EAST 1362.76 feet along an existing fence line; thence SOUTH 89 degrees 29 minutes 40 seconds EAST 1971.06 feet; thence SOUTH 00 degrees 26 minutes 10 seconds EAST 1312.50 feet to the point of beginning, containing 64.98 acres, more or less.


This certification does not take into consideration additional facts that an accurate and correct title search and/or examination might disclose. Evidence of easements have not been located in the field and are not shown on this survey drawing.

Subject to the above reservation, I hereby certify that the survey work performed on the project shown hereon was performed either by me or under my direct supervision and control and that all information shown is true and correct to the best of my knowledge and belief.

Certified this 3rd day of March, 1988.

Ben E. Bledsoe

Ben E. Bledsoe
Registered Land Surveyor No. S0559
State of Indiana



WYLIE ROAD


JOB NO. 1217-B

Wylie to Langley

Sec. 33

Washington Twp.

SCALE 1"=200'



FILED

MAR 08 1988

Rodney J. Brown
Surveyor Monroe County, Indiana

SE CORNER OF SECTION
33, T10N, R1W
MONROE COUNTY
INDIANA

WYLLIE ROAD

JOB NO. 1217

A part of the Southeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, more particularly described as follows:

COMMENCING at the southeast corner of said section 33; thence NORTH 89 degrees 41 minutes 18 seconds WEST along the south line of said southeast quarter 1489.98 feet to the point of beginning; thence NORTH 00 degrees 26 minutes 41 seconds WEST 1317.55 feet to an existing fence line; thence along said fence line NORTH 89 degrees 29 minutes 40 seconds WEST 480.81 feet to a fence corner; thence along said fence line SOUTH 14 degrees 51 minutes 39 seconds WEST 1362.76 feet to the south line of said southeast quarter; thence along said south line SOUTH 89 degrees 41 minutes 18 seconds EAST 840.55 feet to the point of beginning, containing 20.0 acres, more or less.

This certification does not take into consideration additional facts that an accurate and correct title search and/or examination might disclose.

Evidence of easements have not been located in the field and are not shown on this survey drawing.

Subject to the above reservation, I hereby certify that the survey work performed on the project shown hereon was performed either by me or under my direct supervision and control and that all information shown is true and correct to the best of my knowledge and belief.


Certified this 12th day of February, 1988.

Ben E. Bledsoe

Ben E. Bledsoe

Registered Land Surveyor No. S0559

State of Indiana




6810 N SHOWERS ROAD

REVIEWED

By Cassidy Raley at 2:30 pm, Jan 04, 2018

"HOUSE DETAIL"
SCALE 1" = 30'



Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana November 9, 1989

DESCRIPTION:

A part of the Southeast quarter of the Southwest quarter of Section 33, Township 10 North, Range 1 West, and a part of the Northwest quarter of the Northeast quarter of Section 4, Township 9 North, Range 1 West, Monroe County, Indiana, as recorded in Deed Record 322 at page 376 and being more particularly described as follows:

A part of the Southeast quarter of the Southwest quarter in Section 33, Township 10 North, Range 1 West, and a part of the Northwest quarter of the Northeast quarter in Section 4, Township 9 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point that is 708.15 feet South of the Northwest corner of the Northwest quarter of the Northeast quarter in Section 4, Township 9 North, Range 1 West and in the centerline of Showers Road, thence running with said centerline North 00 degrees 21 minutes 28 seconds West for 457.44 feet, thence North 05 degrees 09 minutes 25 seconds East for 63.86 feet, thence North 10 degrees 57 minutes 51 seconds East for 61.41 feet, thence North 26 degrees 16 minutes 26 seconds East for 146.97 feet, thence North 42 degrees 49 minutes 18 seconds East for 58.59 feet and to the intersection of Showers road and Wylie road, thence running with said Wylie road centerline South 78 degrees 16 minutes 01 second East for 77.54 feet, thence leaving said road centerline and running South 00 degrees 21 minutes 28 seconds East for 740.33 feet, thence West for 200.00 feet and to the point of beginning. Containing in all 3.18 acres, more or less. Subject to a 25.00 foot easement from the centerline of said Showers Road and Wylie road for County Highway right-of-way.

CERTIFICATION:

I hereby certify that this plat as shown is a true and complete survey of the described property, and further certify that all improvements are wholly within the boundaries of said described property, and that the said improvements do not encroach upon any other property, nor are there any encroachments from any other property on said surveyed property.

NW CORNER
NW 1/4, NE 1/4
SECTION 4
T9N, R1W

N10°57'51"E

N05°09'25"E

SHOWERS ROAD


W182°12'00"W

708.15' SOUTH
NW CORNER
NW 1/4, NE 1/4
SECTION 4
T9N, R1W

SECTION 33

N42°49'18"E
N26°16'26"E
N46°02'16"E
N42°49'18"E
S78°16'01"E
77.54'

3.09 A
3.18 ACRES



SCALE
1" = 100'

1489 W. LAWSON
BIGN, IND. 47401

REVIEWED

By Cassidy Raley at 2:27 pm, Jan 17, 2018

EXECUTOR'S DEED

BYRON K. SMITH, as personal representative of the Estate of Cleo K. Smith, deceased, which estate is under the supervision of the Circuit Court of Monroe County, under Estate No. 53C01-8808-ES-00133, in the Office of the Clerk of the Circuit Court of Monroe County, Indiana, pursuant to an order of the Monroe Circuit Court of Monroe County, Indiana, dated on the 1st day of February, 1989, for good and sufficient consideration, CONVEYS TO:

BEVERLY A. SAMPLE,
1489 Lawson Rd., Bloomington, IN 47401

of Monroe County, State of Indiana, the following described real estate in Monroe County, State of Indiana, to-wit:

A part of the Northwest quarter of the Northwest quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point that is 660 feet West of the Northeast corner of said quarter quarter in said Section 33 and in Lawson Road, thence leaving said road and running South 00 degrees 42 minutes 41 seconds West for 1306.63 feet, thence West for 248.45 feet, thence North 11 degrees 22 minutes 33 seconds West for 192.81 feet, thence North 01 degree 16 minutes 39 seconds East for 350.74 feet, thence North 08 degrees 28 minutes 08 seconds East for 74.62 feet, thence North 16 degrees 03 minutes 55 seconds East for 721.20 feet and to a point in Lawson Road, thence running in said road East for 84.30 feet and to the point of beginning. Containing 6.81 acres, more or less.

Grantor conveys to Grantee the right to use a non-exclusive driveway easement 30 feet in width as now located and used on the West side of the above described real estate.

Grantor reserves the right to use said driveway easement as above described.

Subject to a 25-foot easement from the centerline of Lawson Road for County Highway right-of-way over the North side of said real estate.

Subject to an easement executed on the 11th day of April, 1967, by Lucy Davidson to Indiana Statewide Rural Electric Cooperative, Inc., (The Hoosier Energy Division) and recorded on the 16th day of May, 1967, in Deed Record 177, pages 278-279, in the office of the Recorder of Monroe County, Indiana.

Subject to an Electric Pole Line Easement executed on the 18th day of June, 1956, by Charley A. Terrell and Leola Agnes Terrell to Public Service Company of Indiana, Inc., and recorded in Deed Record 120, page 467, in the office of the Recorder of Monroe County, Indiana.

Subject to all taxes, liens, and assessments.

IN WITNESS WHEREOF, the said BYRON K. SMITH, as personal representative of the Estate of Cleo K. Smith, deceased, has hereunto set his hand and seal this 1st day of February, 1989.

BYRON K. SMITH (SEAL)

BYRON K. SMITH, EXECUTOR OF THE
ESTATE OF CLEO K. SMITH, DECEASED

EXAMINED AND APPROVED IN OPEN
COURT, THIS 1st DAY OF
February, 1989.

James M. Dwyer
JUDGE, MONROE CIRCUIT COURT


PT NW 1/4 SECT. 34 & PT NE 1/4 SECT. 33

REVIEWED

By Cassidy Raley at 2:30 pm, Jan 17, 2018

NW CORNER SECTION 34 & NE CORNER SECTION 33 T10N, R1W

(TILLIAND
(TROY)



Working 33 & 34

1.65 AC SECT. 34
0.04 AC SECT. 33
1.69 AC. TOTAL

DESCRIPTION:

A part of the Northeast quarter of Section 33 and a part of the Northwest quarter of Section 34, Township 10 North, Range 1 West, Monroe County, Indiana, described as follows:

Beginning at a point that is 87.55 feet East of the Northeast corner of Section 33 (also being the Northwest corner of Section 34) and on the North line of Section 33; thence running East along the North line of said Section 34 for a distance of 220.08 feet; thence leaving said North line and running South 26 degrees 57 minute:


40 seconds West for a distance of 491.28 feet and to the centerline of Sample Road; thence running along said centerline North 58 degrees 04 minutes 17 seconds West for a distance of 100.00 feet and to a point on the West line of Section 34 (also being the East line of Section 33); thence continuing along said road centerline North 56 degrees 49 minutes 20 seconds West for a distance of 36.88 feet; thence leaving said centerline and running North 17 degrees 58 minutes 50 seconds East for a distance of 383.61 feet to the point of beginning.

Containing: 1.65 acres in Section 34
0.04 acre in Section 33
1.69 acres total



Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
December 17, 1990



REVIEWED

By Cassidy Raley at 2:30 pm, Jan 17, 2018

Edward Gilliland +
Ronald Gilliland



Scale 1" = 50'

Walling for 33 & 34

DESCRIPTION:

A part of the Northwest quarter of Section 34, Township 10 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at the northwest corner of said Section 34, thence running on the North line of said Section East for 87.55 feet, thence leaving said north line and running South 17 degrees 58 minutes 50 seconds West for 283.61 feet and to a point on the West line of said section 34 said point being 269.76 feet South of the Northwest corner of said section, thence running North on the West line of said section for 269.76 feet and to the point of beginning. Containing in all 0.27 acres, more or less.





Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
December 11, 1990

REVIEWED

By Cassidy Raley at 2:30 pm, Jan 17, 2018




RON GILLILAND
TO
TROY GILLILAND

0.04 ACRES

33134


DESCRIPTION:

A part of the Northeast quarter of Section 33 Township 10 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point on the East line of said Section 33, thence running on the said section line South for 115.30 feet and to the centerline of Sample Road, thence leaving said section line and running with the centerline of said road North 56 degrees 49 minutes 20 seconds West for 36.88 feet, thence leaving said road centerline and running North 17 degrees 58 minutes 50 seconds East for 100.00 feet and to the point of beginning. Containing in all 0.04 acres, more or less. Subject to a 25.00 foot easement from the centerline of said Sample Road for County Highway right-of-way.



Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
December 17, 1990




DESCRIPTION:

A part of the Northeast quarter of Section 33 and a part of the Northwest quarter of Section 34 all being in Township 10 North, Range 1 West, Monroe County, Indiana, and being more particularly described as follows: Beginning at the Northwest corner of said Section 34, thence running on the North line of said Section East for 87.55 feet, thence leaving said section line and running South 17 degrees 58 minutes 50 seconds West for 283.61 feet and to a point on the East line of said Section 33 that is 269.76 feet South of the Northeast corner of said section 33, thence leaving said section line South 17 degrees 58 minutes 50 seconds West for 100.00 feet and to the centerline of Sample Road; thence

running in said centerline North 56 degrees 49 minutes 20 seconds West for 145.82 feet, thence north 58 degrees 11 minutes 37 seconds West for 395.07 feet, thence leaving said road centerline and running with an existing wood fence North 01 degree 31 minutes 42 seconds East for 76.85 feet and to the North line of said Section 33, thence running with said North section line East for 486.65 feet and to the point of beginning. Containing in all 2.80 acres, more or less. Subject to a 25.00 foot easement from the centerline of said Sample Road for County Highway right-of-way.

CERTIFICATION:

I hereby certify that this plat as shown is a true and complete survey of the described property, and further certify that all improvements are wholly within the boundaries of said described property and that the said improvements do not encroach upon any other property, nor are there any encroachments from any other property on said surveyed property.



Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
December 11, 1990


Pt NE 1/4 SECT. 33, T10N, R

REVIEWED

By Cassidy Raley at 2:30 pm, Jan 17, 2018

RON GILLILAND TO LEON WEAVER

0.15 ACRE



DESCRIPTION:

A part of the Northeast quarter of Section 33, Township 10 North, Range 1 West, Monroe County, Indiana, bounded and described as follows: Beginning at a point on the North line of said Section 33 that is 685.65 feet West of the Northeast corner of said section, thence leaving said section line and running South 01 degree 31 minutes 42 seconds West for 76.85 feet and to the centerline of Sample Road, thence running with said road centerline North 60 degrees 44 minutes 22 seconds West for 85.89 feet, thence in said centerline North 74 degrees 16 minutes 52 seconds West for 128.49 feet and to a point where said centerline intersects with the North line of said Section 33, thence leaving said road centerline and running with said section line East for 200.73 feet and to the point of beginning. Containing in all 0.15 acres, more or less. Subject to a 25.00 foot easement from the centerline of said Sample Road for County highway right-of-way.



Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
December 17, 1990